

Project Verification Report

2021

COVER PAGE	
Project Verification Report Form (VR)	
BASIC INFORMATION	
Name of approved UCR Project Verifier / Reference No.	Enviance Services Private Limited
Type of Accreditation	☐ CDM or other GHG Accreditation ☒ ISO 14065 Accreditation
Approved UCR Scopes and GHG Sectoral scopes for Project Verification	01 Energy industries (Renewable/Non-Renewable Sources)
Validity of UCR approval of Verifier	30/09/2027
Completion date of this VR	21/02/2026
Title of the project activity	50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana
Project reference no. (as provided by UCR Program)	UCR 542
Name of Entity requesting verification service (can be Project Owners themselves or any Entity having authorization of Project Owners, example aggregator.)	Viviid Emissions Reductions Universal Pvt. Ltd.
Contact details of the representative of the Entity, requesting verification service (Focal Point assigned for all communications)	Name: Lokesh Jain Email ID – lokesh.jain@viviidgreen.com
Country where project is located	India
Applied methodologies (approved methodologies by UCR Standard used)	ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0
GHG Sectoral scopes linked to the applied methodologies	01 Energy industries (Renewable/Non-Renewable Sources)
Project Verification Criteria:	☒ UCR Standard

Mandatory requirements to be assessed	☒ Applicable Approved Methodology ☒ Applicable Legal requirements /rules of host country ☒ Eligibility of the Project Type ☒ Start date of the Project activity ☒ Meet applicability conditions in the applied methodology ☒ Credible Baseline ☒ Do No Harm Test ☒ Emission Reduction calculations ☒ Monitoring Report ☒ No GHG Double Counting ☐ Others (please mention below)
Project Verification Criteria: Optional requirements to be assessed	☒ Environmental Safeguards Standard and do-no-harm criteria ☒ Social Safeguards Standard do-no-harm criteria
Project Verifier's Confirmation: The <i>UCR Project Verifier</i> has verified the UCR project activity and therefore confirms the following:	The UCR Project Verifier Enviance Services Private Limited, certifies the following with respect to the UCR Project Activity 50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana ☒ The Project Owner has correctly described the Project Activity in the Project Concept Note version 1.2 (dated 17/02/2026) including the applicability of the approved methodology <i>ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources</i> -

	Version 22.0 and meets the methodology applicability conditions and has achieved the estimated GHG emission reductions, complies with the monitoring methodology and has calculated emission reductions estimates correctly and conservatively. ☒ The Project Activity is likely to generate GHG emission reductions amounting to the estimated 83,827 tCO_{2e} annually, as indicated in the PCN, which are additional to the reductions that are likely to occur in absence of the Project Activity and complies with all applicable UCR rules, including ISO 14064-2 and ISO 14064-3. ☒ The Project Activity is not likely to cause any net-harm to the environment and/or society ☒ The Project Activity complies with all the applicable UCR rules¹ and therefore recommends UCR Program to register the Project activity with above mentioned labels.
Project Verification Report, reference number and date of approval	Verification Report UCR Reference number: 542 Date of approval: 05-05-2026

¹https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com//Documents/UCRtermsandconditionsMay2025Ver11_230525172325112351.pdf

Name of the authorised personnel of UCR Project Verifier and his/her signature with date



Vidhya Muralikrishna
Quality Manager
Date: 05-05-2026

PROJECT VERIFICATION REPORT

Executive summary

The project activity is titled- “50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana”. It is a solar-power Project which is located in Pedayyipally, Kamareddy District in the South side of Hyderabad in Telangana, India. The project activity aims to harness solar radiation, a renewable energy source, to generate electricity for supply to Telangana grid by the project proponent (PP), M/S Sunshakti Solar Power projects private Limited. The project consists of ground mounted photo voltaic solar plant with aggregated installed capacity of 50 MW, located in Telangana, India, to generate clean energy and reduce greenhouse gas (GHG) emissions. This project comprises of solar panels spread across Pedayyipally village.

The solar project generates approximately 631,307 MWh of clean electricity in the current monitoring period. The power produced by the 50MW is evacuated at 132 KV level with Interconnection Point at 220/132 KV Kamareddy SS.

Name of the project	Interconnection Substation	Injection Voltage	Interconnection Point	Type of Project	Capacity of the Project (MW)
M/s. SunShakthi Solar Power Projects Pvt. Ltd.	220/132 KV SS Kamareddy	132 KV	132 kV side at the 220/132 KV SS Kamareddy	Solar Photovoltaic	50 MW

The generated Power is being sold to Telangana State Northern Power Distribution Company Limited (TSNPDCL). This process ensures the generated solar power is integrated into the larger power supply system. The power purchase agreement is valid for a period of 20 years, aligned with the operational lifetime of the project activity, and outlines the terms and conditions for energy injection, transmission losses, scheduling, and settlement.

The expected operational lifetime of the project is for 25 years. Addressing the energy demand-supply gap in Telangana and supporting the region’s sustainable growth.

The solar plant has been operational since 02/11/2017. The project has been operational since the earliest commissioning date.

This project activity was not registered in any other registries prior to its registration in UCR. PP seeks verification under UCR from 02/11/2017 onwards, i.e., crediting period for UCR starts from 02/11/2017. Hence, there is no double counting for said projects.

Commissioning dates of the project activity are mentioned in the table below:

Name	Plant capacity	Site	Commissioning Date
M/S Sunshakti Solar Power projects private Limited	50MW	Pedayyipally	02/11/2017

Geo Co-ordinates of the project activity are mentioned in the table below:

Name	Plant capacity	Site	Geo-coordinate
M/S Sunshakti Solar Power projects private Limited	50MW	Pedayyipally	18.22° N and 78.32° E

Proposed solar power project has evolved as a result of the policies of Government of India and Government of Telangana, which encourages energy development from renewable sources. These policies have given fresh impetus to solar power generation.

The Project Activity is a greenfield solar project and the net generated electricity from the project activity is being provided to the Telangana State Northern Power Distribution Company Limited (TSNPDCL) by the project proponent. A Power Purchase Agreement is signed between the project proponent and Telangana State Northern Power Distribution Company Limited (TSNPDCL). The project activity involves a Ground-Mounted Photovoltaic (PV) Solar Power Plant with a total installed capacity of 50 MW. The project utilizes Polycrystalline and Monocrystalline solar photovoltaic technologies to generate clean, renewable energy.

The project consists of ground mounted photo voltaic solar plant with a installed capacity of 50 MW. The plant was commissioned by the respective authority of government of Telangana. The project generates clean energy by utilizing the solar Radiations.

The applied technology is considered to be one of the most environment friendly technologies available as the operation of the Solar photovoltaic does not emit any GHGs or any other harmful gases unlike the operation of conventional power plants. Photovoltaic module consists of several photovoltaic cells connected by circuits and sealed in an environmentally protective laminate, which forms the fundamental building blocks of the complete PV generating unit. Several PV panels mounted on a frame are termed as PV Array.

The generation of power from solar photovoltaics is a clean technology as there is no fossil fuel-fired or no GHG gases are emitted during the process. A photovoltaic module consists of several photovoltaic cells connected by circuits and sealed in an environmentally protective laminate, which forms the fundamental building blocks of the complete PV generating unit. Several PV panels mounted on a frame are termed PV Array. Thus, project activity leads to a reduction the GHG emissions as it displaces power from fossil fuel-based electricity generation in the regional grid. Since the project activity generates electricity through solar energy, a clean

renewable energy source it will not cause any negative impact on the environment and thereby contributes to climate change mitigation efforts.

The project also incorporates a Supervisory Control & Data Acquisition (SCADA) system, which provides a graphical representation of operational data, long-term data storage, and historical analysis. It facilitates access to daily generation reports and power curve monitoring while enabling both real-time and offline troubleshooting with advanced analytical tools.

Without this project, the amount of electricity generated would come from fossil fuel-based power plants, which is the baseline scenario. This renewable energy project reduces emissions and supports local manufacturing through technology transfer.

The Plant Load Factor has been determined by taking the normative benchmark as 21.64% as per DPR. The project being a renewable energy generation activity, leads to reduction in fossil fuel dominated electricity generation from the Indian grid.

The core objective of this project activity is to displace an equivalent amount of electricity which would have otherwise been generated by fossil fuel dominant electricity grid. The estimated lifetime of the project activity is considered as 25 years for solar technology. In the Pre- project scenario the entire electricity, consumed by the customers or delivered to the grid by, would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources.

This project generates 50 MW power which supplied to the Telangana (Indian) Grid system. The applied technology is one of the most environment friendly technologies available as the operation of the solar power plant does not emit any GHGs or any other harmful gases unlike the operation of conventional power plant. The project activity has used the reliable and proven technology to ensure that an environmentally safe and sound technology has been implemented.

The project activity also contributes to SDG goals 7, 8 and 13.

The first crediting period of the project activity in UCR is 07 years, 10 months, 18 days in which total estimated electricity generation is 93,141 MWh annually and the total GHG emission reduction estimated is 83,827 tCO₂e annually.

The electricity generation for the current monitoring period is 631,307 MWh and total GHG emission reduction is 554,625 tCO₂e.

Scope of Verification

The scope of the services for the project is to perform Project Verification of concerned Project Activity. The scope of verification is to assess the claims and assumptions made in the Project Concept Note (PCN) and Monitoring Report (MR) against the UCR criteria, including but not limited to, UCR program verification guidance document, UCR Standard, UCR Program Manual, and related rules and guidelines established under Program process.

Verification Process and Methodology

The verification process was undertaken by a competent verification team and involved the following,

- Desk review of documents and evidence submitted in context of the reference rules and guidelines issued by UCR,
- Undertaking/conducting site visit/remote audit, interview or interactions with the representative of the project owners/representatives,
- Reporting audit findings with respect to clarifications and non-conformities and the closure of the findings, as appropriate and preparing a draft verification opinion based on the auditing findings and conclusions
- Finalization of the verification opinion (this report)

Desk/Document review

A detailed desk review of the PCN, MR, Methodology and all other associated documentation and references took place in advance of the site visit, and additional documents that were not available for the desk review were requested for review during the site visit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face to face interviews with key stakeholders (including the project developers and where necessary, government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Follow up interviews/site visit

The verifier conducted remote audit and had requested for site photographs, short videos. A remote interview was conducted with the project owners and stakeholders.

Conclusion

Based on the work performed, the verifier concludes that in the project activity “50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana”, the information and data presented in the MR version 1.3 dated 17/02/2026 is in line with the Project Concept Note Version 1.2 date 17/02/2026 and meets all relevant requirements of the UCR for UCR project activities. The UCR project activity correctly applies the methodology “ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0” leading to result in real, measurable and long-term emission reductions achieved for the current monitoring period.

For the current monitoring period, verified emission reductions achieved by the project activity were as below;

Start date of monitoring period	02/11/2017
End date of monitoring period	31/12/2024

Emission reductions achieved	554,625 tCO ₂ eq
------------------------------	-----------------------------

Project Verification team, technical reviewer and approver

Project Verification team

No.	Role	Last name	First name	Affiliation (e.g. name of central or other office of UCR Project Verifier or outsourced entity)	Involvement in		
					Doc review	Off-Site inspection	Interviews
1.	Team Leader/ Lead Verifier	Mahajan	Swati	Enviance Services Private Limited	Yes	Yes	Yes
2.	Validator- Verifier/Technical Expert	Singh	Ritu	Enviance Services Private Limited	Yes	Yes	Yes

Technical reviewer and approver of the Project Verification report

No.	Role	Type of resource	Last name	First name	Affiliation (e.g. name of central or other office of UCR Project Verifier or outsourced entity)
1.	Technical reviewer	Internal	Kumar	Pankaj	Enviance Services Private Limited
2.	Approver	Internal	Krishna	Vidhya Murali	Enviance Services Private Limited

Means of Project Verification

Desk/document review

A detailed desk review of the PCN, MR, methodology and all other associated documentation and references took place in advance of the remote audit, and additional documents that were not available for the desk review were requested for review during the remote audit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face-to face interviews with key stakeholders (including the project developers and where necessary, Government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Off-site inspection

Date of off-site inspection: 02/09/2025			
No.	Activity performed Off-Site	Site location	Date
1.	a) An assessment of the implementation and operation of the project activity as per the PCN and UCR requirements b) Verification of the project design, as documented is sound and reasonable, and meets the identified criteria of UCR Standard Requirements and associated guidance c) Assessment to conformance with the certification criteria as laid out in the UCR Standards; d) Evaluation of the conformance with the certification scope, including the GHG project and baseline scenarios, additionality; GHG sources, sinks, and reservoirs; and the physical infrastructure, activities, technologies and processes of the GHG project to the requirements of the UCR; e) Evaluation of the calculation of GHG emissions, including the correctness and transparency of formulae and factors used; assumptions related to estimating GHG emission reductions; and uncertainties; and determination whether the project could reasonably be expected to achieve the estimated GHG reduction/removals. f) Review of information flows for generating, aggregating and reporting of the parameters to be monitored g) To confirm that the operational and data collection procedures can be implemented in accordance with the Monitoring Plan h) Cross-check of information provided in the submitted documents and data from other sources available at site i) Review of calculations and assumptions made in determining the GHG data and estimated ERs, and an identification of QA/QC procedures in place to prevent, or identify and correct, any errors or omissions in the reported monitoring parameters	Pedayyipally, Kamareddy District in the South side of Hyderabad in Telengana, India	02/09/2025

Project Verification Report

	Interviews of local Stakeholders		
--	----------------------------------	--	--

Interviews

No.	Interview			Date	Subject
	Last name	First name	Affiliation		
1.	Patel	Vidhay	M/S Sunshakti Solar Power projects private Limited	02/09/2025	Project Implementation, Monitoring plan, Project Boundary, Eligibility criteria, Host country requirements, Emission reduction calculations Project implementation, monitoring, Local stakeholder consultation
2.	Singh	Mukesh Kumar			
3.	Mishra	Priya	Viviid emissions reductions universal private Ltd.		
4.	Darne	Minal			
5.	Kacha	Nilesh	Local Stakeholders		
6.	Aathmakuri	Lava Kumar			

Sampling approach

Not Applicable.

Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	No. of CL	No. of CAR	No. of FAR
Green House Gas (GHG)			
Identification and Eligibility of project type	-	-	-
General description of project activity	01	-	-
Application and selection of methodologies and standardized baselines	-	-	-
- Application of methodologies and standardized baselines	-	-	-
- Deviation from methodology and/or methodological tool	-	-	-
- Clarification on applicability of methodology, tool and/or standardized baseline	01	-	-
- Project boundary, sources and GHGs	-	-	-
- Baseline scenario	-	-	-
- Estimation of emission reductions or net anthropogenic removals	01	02	-
- Monitoring Report	-	-	-
Start date, crediting period and duration	-	-	-
Environmental impacts	-	-	-
Project Owner- Identification and communication	01	-	-
Others (please specify)	01	-	-
Total	05	02	-

Project Verification findings

Identification and eligibility of project type

Means of Project Verification	The project has an installation of a 50 MW solar power capacity and hence it qualifies as a large-scale project. This is confirmed based on the commissioning certificates and technical specifications. Since the project is a large-scale project, it has applied approved CDM large scale methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0. The Project owner has used valid MR form available at the UCR website for the preparation of MR for the current project activity. The project has prepared MR in line with UCR guidance and requirements.
Findings	No findings raised.
Conclusion	The UCR-approved format is used for description and the project meets the requirement of the UCR verification standard and UCR project standard. UCR project communication agreement was submitted to the verifier and the same has been verified. Methodology referenced and applied appropriately describing the project type. The eligibility of the project aggregator is verified using the UCR communication agreement, project correctly applies the verification standard, UCR project standard, and UCR regulations. The project activity is overall meeting the requirements of the UCR Verification standard and UCR project standard.

General description of project activity

Means of Project Verification	The project activity involves the operation of a 50 MW of large-scale solar power project and its commissioning date and power evacuation at the grid were verified through the commissioning certificate of the project. The power purchase agreement confirms the companies/entities involved in the agreement for supply of generated electricity from the 50 MW (Pedayyipally, Kamareddy District in the South side of Hyderabad in Telengana, India) project. Assessment team conducted documentation review of the PCN against the UCR program verification standard version 2.0 and UCR CoU Standard (project eligibility criteria) version 7.0 and the UCR-PCN-FORM Version 1.0. By checking the supporting documents, it is confirmed that the project is a greenfield solar power project, the project is located in Telangana State in India. The approximate geo-coordinates of the project locations are mentioned below. <u>Details of Latitude &Longitude for the project site: -</u> <table><tr><th>Name</th><th>Plant capacity</th><th>Site</th><th>Geo-coordinate</th></tr><tr><td>M/S Sunshakti Solar Power projects private Limited</td><td>50MW</td><td>Pedayyipally</td><td>18.22° N and 78.32° E</td></tr></table> Assessment team performed an offsite inspection of project and confirmed that the location described in the PCN are accurate. The Project is a solar power project, to utilize solar energy to generate zero carbon emission electricity which is mainly dominated by fossil fuel power output. The project includes integrated power transmission mechanism, high performance solar PV modules, inverters, set up transformers and module mounting systems, other relay & protection systems, microprocessor based fully automatic control system with user friendly operation and central monitoring system. Quality, Safety and Health plan for construction, installation, commissioning and Operation & Maintenance.	Name	Plant capacity	Site	Geo-coordinate	M/S Sunshakti Solar Power projects private Limited	50MW	Pedayyipally	18.22° N and 78.32° E
	Name	Plant capacity	Site	Geo-coordinate					
	M/S Sunshakti Solar Power projects private Limited	50MW	Pedayyipally	18.22° N and 78.32° E					
	Findings	CL 01 was raised and closed successfully. More information presented in the appendix below.							
	Conclusion	The description of the project activity is verified to be true based on the review of PCN, MR, Commissioning Certificate and power purchase agreement.							

Application and selection of methodologies and standardized baselines

(.a.i) Application of methodology and standardized baselines

Means of Project Verification	The project has taken the reference of CDM methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0. CDM website is referred to check the latest version of the methodology. For the applicability mentioned in the PCN and MR, technical Specification, and commissioning certificate.
Findings	No findings raised.
Conclusion	The methodology applied is appropriately meeting the requirements of UCR and its standardized baseline. The methodology version is correct and valid. The referenced methodology is applicable to project activity.

(.a.ii) Clarification on applicability of methodology, tool and/or standardized baseline

Means of Project Verification	The documents reviewed are CDM methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, UCR Program standard, and UCR Verification Standard.
Findings	CL 03 was raised and closed successfully. More information presented in the appendix below.
Conclusion	The verification team confirms that all the applicability criteria set by the applied CDM methodology and its eligible tools are met. The relevant information against those criteria is also included in the PCN version 1.2 and MR version 1.3. The selected CDM methodology for the project activity is applicable.

(.a.iii) Project boundary, sources and GHGs

Means of Project Verification	Project owner has considered project boundary as per applicable methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, "the spatial extent of this project activity includes the project site and all the power plants connected physically to the electricity system (grid) that the power project is connected to." Review of PCN and MR confirms that project sites and Indian electricity grid system is considered as a project boundary which is appropriate.
Findings	No findings raised
Conclusion	The project boundary is correctly defined in the PCN and MR. GHG sources are correctly identified and reported. The project meets the requirements of UCR project standard, Verification standard and methodology requirements for a boundary, GHG sources.

(.a.iv) Baseline scenario

Means of Project Verification	As per the applied ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0 the baseline scenario is as following: The baseline scenario is that if the project activity is the installation of a Greenfield power plant, the baseline scenario is electricity delivered to the grid by the project activity would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources to the grid. Remote audit conducted and document review showed that in absence of the project activity, the generated electricity would have been supplied by the Indian grid which is dominated by fossil fuel fired plants.
Findings	No findings raised.
Conclusion	The approved baseline methodology has been correctly applied to identify a realistic and credible baseline scenario, and the identified baseline scenario most reasonably represents what would occur in the absence of the proposed UCR project activity. All the assumption and data used by the project participants are listed in the PCN and/or supporting documents. All documentation relevant for establishing the baseline scenario are correctly quoted and interpreted in the PCN. Assumptions and data used in the identification of the baseline scenario are justified appropriately, supported by evidence and can be deemed reasonable.

(.a.v) Estimation of emission reductions or net anthropogenic removal

Means of Project Verification	The project verification team checked whether the equations and parameters used to calculate GHG emission reductions or net anthropogenic GHG removals for PCN and MR are in accordance with applied methodology. Project verification team checked section B.5 and C.5.1 of the PCN & MR respectively to confirm whether all formulae to calculate baseline emissions, project emission and leakage have been applied in line with the underlying methodology. The emission reduction calculation has been carried out as per the CDM methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0 As per the CDM approved ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0 paragraph 57, encompass solely the CO₂ emissions stemming from electricity generation in power plants displaced by the project activity. The methodology operates on the assumption that any electricity generation exceeding baseline levels would have originated from established grid-connected power plants and the integration of new grid-connected power plants. $BE_y = EG_{PJ, y} \times EF_{grid, CM, y}$
--------------------------------------	---

	Where; BE_y : Baseline emissions in year y ($tCO_2/year$) $EG_{PJ,y}$: Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the UCR project activity in year y ($MWh/year$) $EF_{grid,CM,y}$: Combined margin CO_2 emission factor for grid connected power generation in year y (tCO_2/MWh) A "grid emission factor" refers to a CO_2 emission factor (tCO_2/MWh) which will be associated with each unit of electricity provided by an electricity system. The UCR recommends an emission factor of $0.9 tCO_2/MWh$ for the 2013-2023 years as a fairly conservative estimate for Indian projects not previously verified under any GHG program. Also, for the vintage 2021, the combined margin emission factor calculated from CEA database in India results into higher emission than the default value. Hence, the same emission factor has been considered to calculate the emission reduction under conservative approach.² Similarly, for the year 2024, a grid emission factor of $0.757 tCO_2/MWh$ is to be applied. These conservative factors are used to calculate emission reductions. In order to facilitate adoption of authentic baseline emissions data and in keeping with the principle of "conservativeness," all UCR Indian RE projects shall use the new conservative grid emission factor of $0.757 tCO_2/MWh$ in their emission reduction calculations for the 2024 vintage year. https://medium.com/@UniversalCarbonRegistry/ucr-cou-standard-update-2024-vintage-ucr-indian-grid-emission-factor-announced-ddb790cdc603 Project emissions: Regarding project emissions, ACM0002 version 22.0 specifies that only emissions related to fossil fuel combustion, emissions from the operation of geothermal power plants due to the release of non-condensable gases, and emissions from water reservoirs of hydroelectric plants should be taken into account. Since the project involves a wind power project, emissions from renewable energy plants are negligible $PE_y = 0$. Since wind power is a GHG emission free source of energy project emission considered as Zero for the project activity. Leakage Emissions: Leakage, as outlined in ACM0002 version 22.0, para 5.6, is considered to be zero as there is no transfer of energy-generating equipment in the project activity Hence ($LE_y = 0$). Emission reductions: As per approved ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, emission reduction is estimated as difference between the baseline emission and project emission after factoring into leakage. Thus, $ER_y = BE_y - PE_y - LE_y$
--	--

² https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UCRStandardAug2024updatedVer7_020824191534797526.pdf

Where:

ER_y = Emission reductions in year y (t CO₂)

BE_y = Baseline Emissions in year y (t CO₂)

PE_y = Project emissions in year y (t CO₂)

LE_y = Leakage emissions in year y (t CO₂)

Therefore, $ER_y = BE_y$

The earliest commissioning date of the Project is 02/11/2017 when the solar plant was commissioned.

The start date of the crediting period under UCR is considered from 02/11/2017.

For the ease of the calculation, duration of the crediting period in UCR is started from 02/11/2017 to 31/12/2024.

The estimated emission reductions are 83,827 CoUs/yr (83,827 tCO₂eq/yr)

Year	Net Generation	Baseline Emissions	Project Emissions	Leakage	Emission Reductions	EF
	MWh	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ /MWh)
Year 1	94783.20	85304.88	0.00	0.00	85304.88	0.9
Year 2	94309.28	84878.36	0.00	0.00	84878.36	0.9
Year 3	93837.74	84453.96	0.00	0.00	84453.96	0.9
Year 4	93368.55	84031.69	0.00	0.00	84031.69	0.9
Year 5	92901.71	83611.54	0.00	0.00	83611.54	0.9
Year 6	92437.20	83193.48	0.00	0.00	83193.48	0.9
Year 7	91975.01	82777.51	0.00	0.00	82777.51	0.9
Year 8	91515.14	82363.62	0.00	0.00	82363.62	0.9
Total Emission reduction	745127	670615	0	0	670615	
Average Emission Reduction	93141	83827	0	0	83,827	

The actual emission reduction achieved during the first CoU's period (02/11/2017 to 31/12/2024) as per the Project Activity:

Actual Total baseline emission reductions (BE_y)= 554,625 CoUs (554,625 tCO₂eq)

Year	Quantity of net electricity generation supplied by the project activity	Quantity of net electricity generation supplied by the project activity	Emission Factor	Baseline Emissions	Project emissions or actual net GHG removals	Leakage	Emission reductions or net anthropogenic GHG removals by
------	---	---	-----------------	--------------------	--	---------	--

		to the grid in year y	to the grid in year y			by sink		sinks
		[KWh]	[MWh]	(tCO ₂ e /MWh)	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ e)
		[EGfacility, y]	[EGfacility, y]	[EFy]	[Bey]= [EGfacility y]* [EFy]	[PEy]	[LEy]	[ERy]=[Bey] - [PEy]-[LEy]
	Year 1	6204681.6	6204.6816	0.9	5584.213 44	0	0	5584
	Year 2	96551244	96551.244	0.9	86896.11 96	0	0	86896
	Year 3	97894848	97894.848	0.9	88105.36 32	0	0	88105
	Year 4	78047556	78047.556	0.9	70242.80 04	0	0	70243
	Year 5	73248828	73248.828	0.9	65923.94 52	0	0	65924
	Year 6	92955684	92955.684	0.9	83660.11 56	0	0	83660
	Year 7	91639396	91639.396	0.9	82475.45 64	0	0	82475
	Year 8	94765000	94765	0.757	71737.10 5	0	0	71737
	Total		631307.237 6					554625
Findings	CL 05, CAR 01 and CAR 02 were raised and closed successfully. More information presented in the appendix below.							
Conclusion	In summary, the calculation of emission reductions was correctly demonstrated by the PP according to the methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0. It is confirmed by the assessment team that: (a) All assumptions made for estimating GHG are listed in the PCN; (b) All documentation used by the project participants as the basis for assumptions and source of data is correctly quoted and interpreted in the PCN (c) All values used in the PCN including GWPs are considered reasonable in the context of the proposed UCR project activity; (d) The methodologies and, where applicable, the standardized baselines and the other methodological regulatory documents have been applied correctly to calculate baseline, project and leakage GHG emissions, as well as GHG emission reductions; (e) All estimates of the baseline GHG emissions can be replicated using the data and parameter values provided in the PCN;							

Means of Project Verification	Parameters determined- Ex-ante							
	The following parameters are determined ex-ante and verified by the verification team:							
	The baseline emission factor ($EF_{grid, y}$) of the project is reported to be determined ex-ante and would remain fixed for the crediting period. A "grid emission factor" refers to a CO ₂ emission factor (tCO ₂ /MWh) which will be associated with each unit of electricity provided by an electricity system. The UCR recommends an emission factor of 0.9 tCO ₂ /MWh for the 2013-2023 years as a fairly conservative estimate for Indian projects not previously verified under any GHG program. Also, for the vintage 2021, the combined margin emission factor calculated from CEA database in India results into higher emission than the default value. Similarly, for the year 2024, a grid emission factor of 0.757 tCO ₂ /MWh is to be applied. These conservative factors are used to calculate emission reductions.							
	In order to facilitate adoption of authentic baseline emissions data and in keeping with the principle of “conservativeness,” all UCR Indian RE projects shall use the new conservative grid emission factor of 0.757 tCO ₂ /MWh in their emission reduction calculations for the 2024 vintage year							
	Hence, the same emission factor has been considered to calculate the emission reduction under conservative approach. The parameters applied in the calculation were validated by the verification team. The verification team confirms that all relevant parameters have been sufficiently considered and the values of the parameters are real, measurable and conservative.							
	Parameters monitored ex-post							
	According to the approved methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, the following parameters will be monitored:							
	<table><tr><th>Parameter</th><th>Description</th></tr><tr><td>$EG_{pj,y}$</td><td>Quantity of net electricity generation supplied by the project plant/unit to the grid in year y</td></tr></table>	Parameter	Description	$EG_{pj,y}$	Quantity of net electricity generation supplied by the project plant/unit to the grid in year y			
	Parameter	Description						
	$EG_{pj,y}$	Quantity of net electricity generation supplied by the project plant/unit to the grid in year y						
The values of the parameters monitored were checked against submitted Joint Meter Readings and invoices and were found correct.								
<u>Meter Details:</u>								
During the calibration of ABT meters on 21.05.2024, it was observed that the backlight of the LCD was not working, and the LCD screen was fading in all Main, Check, and Standby energy meters. Due to this issue, it had become difficult to record JMR (Joint Meter Readings), and the fading LCD screen was also resulting in incorrect billing. Additionally, a few links in the TTB were found to have failed. For this reason, the meter was replaced on 27.12.2024.								
Old Meter								
<table><tr><th>Meter Details</th><th>Main Meter</th><th>Check Meter</th><th>Stand by Meter</th></tr><tr><td></td><td></td><td></td><td></td></tr></table>	Meter Details	Main Meter	Check Meter	Stand by Meter				
Meter Details	Main Meter	Check Meter	Stand by Meter					

	Sl. No.	APX01518	APX01519	APX01520													
	Make	Secure	Secure	Secure													
	Accuracy	Class: 0.2 s	Class: 0.2 s	Class: 0.2 s													
	New Meter																
	Meter Type		Serial No.														
	Main Meter		APZ02558														
	Check Meter		APZ02559														
	Stand By Meter		APZ02560														
	<u>Calibration Details:</u>																
	<table><tr><th>Company Name</th><th>Plant Capacity (MW)</th><th>Location</th><th>Commissioning Date</th><th>Calibration date</th><th>Calibration validity</th><th>Calibration delay</th></tr><tr><td>50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana</td><td>50 MW</td><td>Pedayyipally</td><td>02-11-2017</td><td>18-05-2023 27-12-2024</td><td>18-05-2028 27-12-2029</td><td>01-11-2017 to 17-05-2023</td></tr></table>				Company Name	Plant Capacity (MW)	Location	Commissioning Date	Calibration date	Calibration validity	Calibration delay	50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana	50 MW	Pedayyipally	02-11-2017	18-05-2023 27-12-2024	18-05-2028 27-12-2029
Company Name	Plant Capacity (MW)	Location	Commissioning Date	Calibration date	Calibration validity	Calibration delay											
50 MW Solar Project by Sunshakti Solar Power Projects Pvt Ltd in Telangana	50 MW	Pedayyipally	02-11-2017	18-05-2023 27-12-2024	18-05-2028 27-12-2029	01-11-2017 to 17-05-2023											

There was a calibration delay from 01-11-2017 to 17-05-2023 in the monitoring period. To address this, an error factor has been applied to the net export values for the delay period since the meters were not calibrated as per the required frequency. According to VVS guidelines, an error factor of "±0.2%" should be applied separately to both export and import values. A conservative approach has been adopted. To account for potential errors in both export and import, a cumulative error factor of "-0.4%" has been applied to the net electricity generation for the delay period. ³

Calibration of meters was done as per the CEA regulations.

Management system and quality assurance

The monitoring plan presented in the PCN complies with the requirements of the applicable methodology. The verification team has verified all parameters in the monitoring plan against the requirements of the methodology and no deviations have been found.

The management system and quality assurance procedures have been reviewed by the verification team through document review and interviews with the project participant. The project participant would train all the monitoring staffs are trained against with related requirement; the training guidelines and monitoring manual are saved and verified.

The monitoring plan outlines in the PCN includes:

³ https://cdm.unfccc.int/sunsetcms/storage/contents/stored-file-20210921115831128/reg_stan06_v03.0.pdf?

	- Monitoring Organization - Monitoring apparatus and installation - Calibration - Data collection - Data Management system The submitted calibration certificates were checked and it was confirmed that the calibrations are conducted periodically as specified in the PCN i.e. at least once in 5 years.
Findings	No findings raised.
Conclusion	The verification team is convinced of compliance of the monitoring plan with the requirements of the monitoring methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0. During the remote audit assessment, the verification team interviewed the PP that the monitoring arrangements described in the monitoring plan are feasible within the project design. The monitoring parameter reported in MR adequately represents the parameters relevant to emission reduction calculation. The calibration report ensures the accuracy of the data reported. The number of CoUs generation is calculated based on this accurately reported data. The calculation was done using an excel sheet where all the parameters were reported. The grid emission factor for electricity is considered as per UCR recommendation for Indian project. In the monitoring report, emission reduction calculations are correctly calculated and reported. The monitoring report meets the requirements of UCR project verification requirements.

Start date, crediting period and duration

Means of Project Verification	The start date and crediting period of project activity was checked based on the commissioning certificate, PCN, MR and other documents provided.
Findings	No findings raised.
Conclusion	The project has chosen crediting period start date in UCR as 02/11/2017. The crediting period is chosen as 02/11/2017 to 31/12/2024 and the crediting period for the current monitoring period is 02/11/2017 to 31/12/2024.

Positive Environmental impacts

Means of Project Verification	PP has not claimed any separate positive environmental impact. The project being renewable energy project will reduce fossil fuel use through replacement of the same.
Findings	No findings raised
Conclusion	The project is a renewable energy project and reduces the environmental burden by reducing the dependence on fossil fuel-based power plants.

Project Owner- Identification and communication

Means of Project Verification	PCN, communication agreement, MR, commissioning certificate, power purchase agreement.
Findings	CL 04 was raised and closed successfully. More information presented in the appendix below.

Conclusion	The project owner was identified through a communication agreement signed between project owner and project aggregator. Commissioning certificates and Power Purchase Agreement were also verified and they clearly establish the project ownership. The identification and communication correctly meet the requirement of project verification and UCR project standard. Project owner: M/S Sunshakti Solar Power projects private Limited.
-------------------	---

Positive Social Impact

Means of Project Verification	Project has provided temporary employment to local people during its installation and commissioning. Also post commissioning some of people have employed permanently and local people were engaged leading to social financial benefit to surrounding. Overall social impact of project implementation is positive on the surrounding area
Findings	No findings raised.
Conclusion	Project has overall positive social impact

Sustainable development aspects (if any)

Means of Project Verification	PP has claimed SDG Goals 7, 8 & 13. SDG 7 is affordable and clean energy and it is verified during remote audit as the project is wind power plant. SDG 8 is decent work & economic growth and is verified by the supporting documents provided. SDG 13 is climate action. These claims were checked on the basis of supporting documents, JMR & invoice, employment of the local people on the project site and emission reduction calculations respectively.
Findings	CL 02 was raised and closed successfully. More information presented in the appendix below.
Conclusion	The project has the capability to address SDG 7, 8 and 13.

Internal quality control

The verifier confirms that,

- Due professional care has been taken while reviewing the submitted document.
- There is no conflict of interest as the verifier has no other engagement with either the aggregator or project owner directly or indirectly.
- Verification team consists of experienced personnel.

Project Verification opinion

Assessment team conducted documentation review the PCN against the UCR program verification standard version 2.0 and UCR project eligibility criteria version 7.0 and the UCR-PCN-FORM Version 1.0.

It is confirmed that the project activity is a 50 MW of large-scale solar power project located across Pedayyipally, Kamareddy District in the South side of Hyderabad in Telangana in India.

The geo co-ordinates of the project activity have been mentioned in sections above. Assessment team performed a remote audit and confirmed that the location described in the PCN is accurate. The verification was performed on the basis of UCR requirements, and host country criteria, as well as criteria given to provide for consistent project operations, monitoring and reporting.

The verification consisted of the following three phases: i) desk review of the PCN, MR and additional background documents; ii) follow-up interviews with project stakeholders; iii) resolution of outstanding issues and the issuance of the final verification report and opinion.

The project correctly applies the approved baseline and monitoring methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0.

The monitoring plan provides for the monitoring of the project's emission reductions. The monitoring arrangements described in the monitoring plan are feasible within the project design, and the project participants are able to implement the monitoring plan. Given that the project is implemented and maintained as designed, the project has achieved the emission reductions of 554,625 tCO₂eq during the monitoring period i.e. from 02/11/2017 to 31/12/2024.

The review of the project design documentation and the subsequent follow-up interviews have provided assessment team with sufficient evidence to determine the fulfilment of stated criteria. In our opinion, the project meets all applicable UCR requirements. Assessment team thus requests the registration of the proposed UCR project activity.

Appendix 1. Abbreviations

Abbreviations	Full texts
ACM	Approved Consolidated Methodology
UCR	Universal Carbon Registry
PCN	Project Concept Note
MR	Monitoring Report
t	Tonnes
NGO	Non-Governmental Organization
ISO	International Organization for Standardization
CAR	Corrective Action Request
CL	Clarification Request
GHG	Greenhouse Gas
MWh	Megawatt Hours
CO ₂	Carbon Dioxide
CH ₄	Methane
N ₂ O	Nitrous Oxide

Appendix 2. Competence of team members and technical reviewers

❖ **Mr. Pankaj Kumar** is a seasoned Environment and Climate Change professional with over 19 years of experience in Climate Change Mitigation & Adaptation, Environmental Due Diligence, Disaster Risk Reduction, Climate Finance, and capacity building. As the Managing Director of Enviance Services Pvt. Ltd., Pankaj Kumar leads a validation and verification body for GHG projects and also providing consultancy services in various areas including Climate Adaptation, Mitigation, Sustainability, and more. Previously, Pankaj Kumar served as a Climate Adaptation Expert with Deloitte Touche Tohmatsu India LLP, contributing to the World Bank project on Asset Management, Institutional Effectiveness, and Road Safety in Bihar. Mr. Pankaj also led the Bihar team for the South Asia Climate Proofing and Growth Development (CPGD) – Climate Change Innovation Programme (CCIP), supported by DFID, which aimed to integrate climate change resilience into planning and budgeting across South Asia. With a strong background in environmental projects, Pankaj Kumar has worked with IL&FS Infrastructure Development Corporation and BUIDCO (Bihar Urban Infrastructure Development Corporation) as an Environmental Specialist for WB & ADB funded projects. Additionally, Pankaj has extensive experience in GHG project validation and verification, having led over 300 projects globally while with UNFCCC accredited DoEs and as an external expert for Gold Standard and Global Carbon Council. Mr. Pankaj is an accredited Lead Auditor, Validator, Verifier, and Technical Expert for multiple sectoral scopes by UNFCCC DoE and is on the roster of WASH experts of UNICEF. Mr. Pankaj's expertise spans across various standards including CDM, Verified Carbon Standard, Gold Standard, Global Carbon Council, Natural Forest Standard, Riverse and Social Carbon Standard.

❖ **Ms. Ritu Singh** has done Masters in Environmental Science from Central University of South Bihar, Gaya and bachelor of Science in Zoology from Magadh Mahila College, Patna University, India. She has done Masters' research focused on solid waste management during and post covid-19 pandemic and conducted a survey in Medical Colleges of Bihar to study the trends of waste management. She has more than 2 year working experience in True Quality Certifications Pvt. Ltd. (An outsource entity for LGAI Technological Center, S.A. (Spain) "Applus+ Certification") and has been involved in supporting Audit teams for Validation and Verifications of Project Activities (Renewable and non-Renewable projects) under CDM/VCS/GS4GG/GCC programs. Currently, Ritu is engaged as an internal resource with Enviance Services Private Limited, where she is accredited as a Lead Auditor, Validator, Verifier, and Technical Expert for Sectoral Scope/Technical Area 1.2 by Enviance.

❖ **Ms. Swati Mahajan** is graduate in Environmental Engineering from Shivaji University, India and previously worked as an Environment Engineer at Eco Designs India Private Ltd., Pune. She is adept in designing of landfill sites for solid waste management. She also has hands on experience in cost benefit analysis and preparation of DPRs for SWM projects. She also has done a certified course in carbon capture and storage from Edinburg University. Currently working as GHG assessor for projects under various GHG mechanisms like GCC, ICR, UCR and VERRA.

Appendix 3. Document reviewed or referenced

No.	Author	Title	References to the document	Provider
1	NA	Communication agreement		Project Owner
2	NA	Project Concept Note		Aggregator
3	NA	Monitoring report		Aggregator
4	NA	Emission reduction sheet		Aggregator
5	NA	Declaration on avoidance of doublecounting		Aggregator
6	NA	Commissioning Certificates for the wind power plants		Aggregator
7	NA	Power purchase agreement		Aggregator
8	NA	Joint Meter Readings/invoices for the complete monitoring period		Aggregator
9	NA	Calibration certificates for energy meters		Aggregator
10	NA	Equipment purchase order		Aggregator
11	NA	Grid Emission factor recommended for Indian projects by UCR	Upto year 2023 - https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UCRStandardAug2024updatedVer7_020824191534797526.pdf Year 2024 - https://medium.com/@UniversalCarbonRegistry/ucr-cou-standard-update-2024-vintage-ucr-indian-grid-emission-factor-announced-ddb790cdc603	General project eligibility criteria and guidance UCR standard version 7.0
12	UCR	UCR Program manual version 6.2 UCR COU standard version 7 UCR Verification standard version 2 UCR terms and conditions version 11.0, May 2025	https://www.ucarbonregistry.io/Document?projectId=1	Universal Carbon Registry
13	CDM	CDM approved methodology- ACM0002- Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0.	https://cdm.unfccc.int/met/hodologies/DB/XB1TX7TAZ6SLWM9B7BC67THHVD16JV	UNFCCC

Clarification request, corrective action request and forward action request

Table 1. CLs from this Project Verification

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	01
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	11/09/2025
PP shall submit a signed copy of undertaking for no double counting for current monitoring period and for project activity has neither been registered nor seeking registration under any other GHG programs.			
Client/Responsible Party/Project Proponent Response		Date:	25/09/2025
PP has submitted the signed copy of no double counting for current monitoring period.			
Validation/Verification Team Assessment		Date:	13/10/2025
PP has submitted the signed copy of no double counting for the current monitoring period. On assessment it was verified that the project activity has neither been registered nor seeking registration under any other GHG programs. Hence, CL 01 is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	02
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	11/09/2025
1. PP shall submit the names of the local stakeholders. 2. The Project Proponent (PP) has claimed alignment with the following Sustainable Development Goals (SDGs): SDG 3: Good Health and Well-being SDG 4: Quality Education SDG 8: Decent Work and Economic Growth In order to validate these claims and ensure measurable achievement of the stated goals, the PP is hereby requested to submit the following supporting documentation: - Evidence of health and safety measures implemented for project workers and surrounding communities (e.g., medical camps, insurance coverage, occupational health programs). - Reports on reduction in pollution or environmental hazards due to project operations. - Initiatives promoting mental and physical well-being at the project site. - Documentation of training programs, skill development workshops, or educational outreach conducted as part of the project. - Partnerships with local schools, colleges, or vocational institutions. - Employment data including number of jobs created, nature of employment (temporary/permanent), and gender inclusivity. All documents should be duly certified and submitted.			
Client/Responsible Party/Project Proponent Response		Date:	25/09/2025
1. PP has submitted the names of the local stakeholders.			

2. PP wants to Clarify that UCR raised a query regarding the location of the CSR activity. The CSR activity is done in GUJARAT state, therefore PP choose to remove these SDG3 & SDG4. PP has submitted SDG8 – which contains Employee List.

SDG 3: ~~Good Health and Well-being~~

SDG 4: ~~Quality Education~~

SDG 8: Decent Work and Economic Growth

Validation/Verification Team Assessment	Date:	13/10/2025
--	--------------	-------------------

- | |
|---|
| <p>1. PP has submitted the list of the names of the local stakeholders.</p> <p>2. The Project Proponent (PP) has clarified that the CSR activity in question was conducted in the state of Gujarat and the project is located in state of Telangana. In response to the query raised by UCR regarding the location of the CSR activity, PP has opted to remove SDG3 and SDG4 from the submission. PP has instead submitted SDG8, which includes the Employee List as supporting documentation. During the assessment, it was verified that the submitted employee list is consistent with and substantiates the SDG8 goal as claimed.</p> |
|---|

Hence, CL 02 is closed.

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	03
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	11/09/2025
1. PP shall submit the meter photographs installed on the project site. 2. As per the submitted calibration certificates, the meters were calibrated on 18/05/2023 with a recalibration due on 17/05/2024. Another certificate indicates calibration on 27/12/2024, valid until 19/02/2026. Given that the monitoring period spans from 02/11/2017 to 31/12/2024, it is observed that the calibration validity does not fully cover the calendar year 2024. Accordingly, the Project Participant (PP) is required to ensure that valid calibration certificates are available for the entire monitoring period. In the absence of continuous calibration coverage for 2024, the PP shall either submit an additional valid calibration certificate covering the gap or apply an appropriate error factor to the monitored data for the affected duration in 2024, in line with applicable regulatory guidelines. 3. PP shall add details of meter calibration, applied error factor and meter serial numbers in MR.			
Client/Responsible Party/Project Proponent Response		Date:	25/09/2025
1. PP has submitted the metres photos & Meter replaced report. Attached in MR. 2. PP wants to clarify that as per CEA, PP has taken once in 5 years for Calibration of meters as CEA guidelines. Therefore, calibration carried out 18/05/2023 to 18/05/2028 will be applicable for that duration and Error factor will be applicable for the period for only 01/01/2013 to 17/05/2023. 3. PP has added meter calibration, applied error factor and meter serial numbers in MR.			
Validation/Verification Team Assessment		Date:	13/10/2025
1. The Project Proponent (PP) has submitted the meter photographs and the meter replacement report, which have been attached in the Monitoring Report (MR). 2. PP has clarified that, in accordance with Central Electricity Authority (CEA) guidelines, meter calibration is conducted once every five years. Based on this, the calibration performed on 18/05/2023 is considered valid until 18/05/2028. Accordingly, the error factor has been applied only for the period from 01/01/2013 to 17/05/2023. 3. The MR has been updated to include details of meter calibration, the applied error factor, and the			

meter serial numbers as required. Hence, CL 03 is closed.
--

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	04
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	11/09/2025
As per the Commissioning Certificate, M/s Sunshakti Solar Power Projects Private Limited is identified as the project company of M/s SkyPower Southeast Asia III Investments Ltd. Also during remote audit it was mentioned that Sunshakti comes under Torrent. In line with regulatory and audit requirements, the Project Proponent (PP) shall furnish the following legal documentation to substantiate ownership and corporate linkage: 1. Certified copy of the Shareholding Structure indicating equity participation by M/s SkyPower Southeast Asia III Investments Ltd. And Torrent 2. Board Resolution or Shareholder Agreement confirming the project company relationship. 3. Memorandum and Articles of Association reflecting the ownership and control provisions. 4. Any relevant documents that establish the ownership hierarchy.			
Client/Responsible Party/Project Proponent Response		Date:	25/09/2025
PP wants to clarify the legal documents are confidential at project owner's end. Therefore, they choose to provide only Board Resolution Relationship documents.			
Validation/Verification Team Assessment		Date:	13/10/2025
The Project Proponent (PP) has clarified that the requested legal documents are confidential at the project owner's end. In response, PP has submitted only the Board Resolution establishing the relationship between M/s Sunshakti Solar Power Projects Private Limited and M/s SkyPower Southeast Asia III Investments Ltd. This document has been provided to substantiate the project company linkage as per audit requirements. During verification, it was confirmed that the submitted Board Resolution is complete and sufficiently establishes the corporate relationship between the entities as required for audit purposes. Hence, CL 04 is closed.			

Classification	☐ CAR	☒ CL/CR	☐ FAR	Number:	05
Raised by:	Ms. Swati Mahajan			Document Reference	MR
Finding Description				Date:	11/09/2025
It has been observed that the next generation values for certain months are recorded as zero. The Project Proponent (PP) is hereby requested to submit a formal explanation detailing the reasons for non-generation during the specified periods.					
The clarification should include, but not be limited to:					
Operational Factors: Scheduled or unscheduled maintenance, grid outages, equipment failure, or commissioning delays. Regulatory or Commercial Constraints: Curtailment instructions from load dispatch centers, lack of power purchase agreements, or tariff-related issues. Environmental or External Conditions: Weather-related disruptions, force majeure events, or site access limitations.					
Supporting documentation such as maintenance logs, grid communication records, or incident reports should be enclosed to substantiate the explanation.					
Client/Responsible Party/Project Proponent Response				Date:	10/10/2025
PP has Submitted the pending JMRs for the year 2023. Few JMRs has not been shared by Project owner due to unavailability of documents. Those Months PP Considered as zero. Above Mentioned Limitations					

are not applicable for this Project activity.		
Validation/Verification Team Assessment	Date:	13/10/2025
The response submitted by the Project Proponent (PP) has been reviewed. It is noted that the zero generation values for certain months were attributed to the non-availability of Joint Meter Reading (JMR) documents from the Project Owner. As per the clarification, these months were recorded as zero in the absence of verifiable data, and the listed operational, regulatory, and environmental constraints were deemed not applicable to the project activity. PP has submitted JMR of 2023 and were verified during assessment and found to be consistent. Hence, CL 05 is closed.		

Table 2. CARs from this Project Verification

Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	01
Raised by:	Ms. Swati Mahajan	Document reference	MR
Finding Description		Date:	11/09/2025
1. Few JMR readings are inconsistent with the submitted supporting documents. Correction sought. 2. PP shall revise the energy generation and emission reduction value in MR (wherever applicable) as per the revised excel sheet.			
Client/Responsible Party/Project Proponent Response		Date:	25/09/2025
1. PP has revised Inconsistent JMR and modified the value in MR. 2. PP has revised the Value and ER value in MR.			
Validation/Verification Team Assessment		Date:	13/10/2025
1. Few JMR readings are still inconsistent with the submitted supporting documents. Correction sought. 2. PP shall revise the energy generation and emission reduction value in MR (wherever applicable) as per the revised excel sheet. Hence, CAR 01 is open.			
Client/Responsible Party/Project Proponent Response		Date:	17/02/2026
1. PP has modified the JMR readings in the ER. 2. PP has revised the value throughout the MR value			
Validation/Verification Team Assessment		Date:	17/02/2026
1. All the JMR readings are now consistent with the submitted supporting documents. 2. PP shall revise the energy generation and emission reduction value in MR (wherever applicable) as per the revised excel sheet. The same was verified in MR version 1.3. Hence, CAR 01 is closed.			

Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	02
Raised by:	Ms. Swati Mahajan	Document reference	MR
Finding Description		Date:	13/10/2025
The calculated values for Estimated Average Generation and Average Emission Reduction appear to be incorrect in the Estimated ER sheet. Correction sought.			

Project Verification Report

Client/Responsible Party/Project Proponent Response	Date:	17/02/2026
PP has made corrections in estimated average generation and emission reduction value.		
Validation/Verification Team Assessment	Date:	17/02/2026
PP has corrected the calculated values for Estimated Average Generation and Average Emission Reduction in the Estimated ER sheet. During assessment it was verified in revised estimated ER sheet and PCN version 1.2. Hence, CAR 02 is closed.		

Table 3. FARs from this Project Verification

FAR ID	xx	Section no.		Date: DD/MM/YYYY
Description of FAR				
Project Owner's response				Date: DD/MM/YYYY
Documentation provided by Project Owner				
UCR Project Verifier assessment				Date: DD/MM/YYYY